No.	Item of work	Per	Quantity
19	Teakwood eave board, plain	R. ft.	279
20	Do ornamental railings with paintings	,,	78
21	Parapet wall complete, 3 feet high as per design	,,	14
22	Chunam borders	,,	20
23	Cornice work, 12" thick	,,	168
24	Flooring with Mangalore tiles over terrace and cement painting, complete	Sqr.	14·54
25	Sillicate painting two coats	,,	7·85
26	Wood oiling to wood work	,,	15·00
27	Teakwood base and caps for pillars as per fresh design	Each	5
28	Do brackets above pillars	,,	7
29	Ornamental end walls with masonry finials pannelling cornice work and plastering, etc., as per fresh design.	,,	2
30	Tower 1st floor architrave with pannelling and chunam mouldings	,,	2
31	Unforeseen items of works		Lump sum
32	Inscription in front of tower at top with chunam		Do
33	Teak wood finials at ends	,,	2
34	Do pendents at corners	,,	4
	LATRINE.		
1	Earthwork excavation	C. yd.	4
2	Burnt brick in mortar	C. ft.	276
3	Do stone slabs, 6" thick	S. ft.	12
4	Chunam plastering	Sqr.	6·21
5	White and colourwashing	,,	6·21
6	Teakwood battend doors, complete	S. ft.	55
7	Constructing seats with brick masonry and plastering and drains		Lump sum
8	Flooring with Cudapah slabs over 3" concrete and cement painting	Sqr.	0·64
9	Coping, complete	R. ft.	43
	STABLE AND COMPOUND WALL.		
1	Earthwork excavation	C. yd.	18
2	Brick in mortar	C. ft.	1,728
3	Burnt stone pillars, 6" thick dressed	S. ft.	2
4	Cutting groves	Each	2
5	Plastering with chunam	Sqr.	27·62
6	Teakwood work wrought and put up	C. ft.	15·41
7	Roofing with Mangalore 1st class tiles over teak reepers, etc.	Sqr.	3·00
8	Chunam borders	R. ft.	30
9	Copings over compound wall	,,	130
10	Whitewashing	Sqr.	27·62
11	Closing the existing wall and clearing site		Lump sum
	EXTENDING EAST SIDE VERANDAH GROUND FLOOR.		
1	Earthwork excavating foundation	C. yd.	7
2	Concrete in mortar	C. ft.	59
3	Burnt brick in mortar	,,	268
4	Burnt stone slabs, 6" thick	S.ft.	23
5	Steel girders including hoisting	Cwt.	3·75
6	Teakwood work wrought and put up	C. ft.	7·29
7	Pucka terrace roof, complete	Sqr.	1·14
8	Cornice, 9" thick	R. ft.	20
9	Flooring with Cudapah slabs over 3" concrete bed and cement painting	Sqr.	0·64
10	Fixing available door including brick masonry and plastering		Lump sum
	EXTENDING EAST SIDE VERANDAH FIRST FLOOR.		
1	Teakwood work wrought and put up	C. ft.	8·29
2	Roofing with Mangalore tiles over teak reepers, etc., complete	Sqr.	0·99
3	Teak wood ornamental railings with painting as per fresh design	R. ft.	8
4	Flooring with Mangalore tiles over terrace and cement painting	Sqr.	0·76
5	Removing windows and refixing door with brick masonry and plastering		Lump sum

H. R. VENKATASUBBA RAO,
Executive Engineer.

WATER SUPPLY DIVISION, BANGALORE.

Dated 28th November 1924.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Water Supply Division, up to the 19th December 1924, for the extension of filter building, Mysore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1925.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office, Water Supply Division, Bangalore, between the hours of 11 A.M. to 5 P.M., on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 500 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for the extension of filter building, Mysore, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Approximate estimate of quantities for the extension of the filter building at Mysore.

No.	Item of work	Per	Quantity
1	Earthwork excavation hard soil	C. yds.	348
2	Filling foundations with surki concrete	C. ft.	295
3	Filling in chunam concrete	"	607
4	Filling foundations with burnt brick in surki mortar	"	1,300
5	Burnt brick in mortar	"	3,802
6	Archwork burnt brick in mortar	"	140
7	Burnt stone slabs 6" thick dressed nicely	S.ft.	221
8	Drilling holes in bed slabs for fixing trusses	No.	24
9	Cement plastering ½" thick	Sqr.	148
10	Burnt stone slabs 4" thick dressed	S.ft.	316
11	Old stone slabs to be used for steps	"	100
12	Chunam plastering	Sqr.	44 60
13	Whitewashing as per interior plastering	"	24·0
14	Colourwashing as per exterior plastering	"	19·80
15	Cast of iron trusses including railway freight 27 feet clear span	No	3
16	Hoisting and fixing charges for trusses	"	3
17	Painting iron trusses	"	3
18	Teakwood doors with pannelled shutters, etc., complete new door	S.ft.	34
19	Removing and refixing existing door including masonry work, etc., complete	No.	1
20	Removing and refixing existing window including masonry work, etc.	"	1
21	Teakwood windows including glazed and pannelled shutters with iron bars, etc., complete	S.ft.	124
22	Removing and refixing old windows	No.	4
23	Teakwood ventilators with iron bars and wire covering, etc., complete new work.	S. ft.	35
24	Removing and refixing old ventilators including circular one	No	5
25	Teakwood work wrought and put up	C. ft.	196·35
26	Roofing with 1st Class Mangalore tiles and ornamental ceiling tiles over teak reepers.	Sqr.	14·23
27	Flooring with 1st class Mangalore tiles over 3" concrete bed including cement pointing, etc. complete.	"	3 45
28	Flooring with 2" teak plank for operating floor including fixing, etc.	S. ft.	391
29	Ornamental parapet wall with brick in chunam and plastering, complete	R. ft.	110
30	Ornamental dental cornice including entablature, etc., complete	"	143
31	Cornice, ordinary	"	112
32	Do 6" at basement	"	111
33	Moulding over windows	"	91
34	Do below do	"	49
35	Pendants	No.	18
36	Ornamental keystone in mortar over doors and windows including plastering, etc	"	11
37	Teakwood finials big for dormor windows	"	4
38	Ornamental masonry finials over pedestals over pillars and gables	"	9
39	Pendants teakwood small for domor windows	"	8
40	White grey pointing	Sqr.	33·48
41	Teakwood steps for platform	S. ft.	23
42	C. I. pillars with base and capitals to support operating floor	No.	6
43	C. I pillars between filters with base and capitals	"	4
44	Handrailing on operating floor	R. ft.	12
45	C. I. gutters for roofing	"	77
46	3" C. I. rain water pipes including head, shoe and offsets, etc., complete	"	120
47	Covered cement drain	"	1 0
48	Dormor windows with glazed shutters (teak)	S. ft.	133
49	Teakwood ornamental eave board	R. ft.	60
50	Ornamental ridge tiles set in mortar	"	62½
51	Do sunshades over door	No.	1
52	Zinc sheet and planking for the valleys of dormor windows including chunam borders, etc., complete.	S. ft.	80
53	Repairs to existing filter building including removing and refixing, roofing, dismantling the side wall and foundations and reconstructing with pillasters and fixing bond stones between old and new wall.	L. S.	Rs.
54	Unforseen charges	"	"
55	Cleaning site and levelling including earthwork	"	"
56	Removing the old steps and relaying the same in front of new door	"	"

M. L. NARASIMHA IYENGAR,
Assistant Engineer (in charge),
Water-Supply Division.